

Subdivision Lines of Township 3 North, Range 32 E. W. M.

Chains 79.80	Intersect East boundary 30 lks. South of corner to Secs. 12 & 13 from which I run S. 89°47'W. on a true line between Secs. 12 & 13
39.90	Set post for $\frac{1}{4}$ Sec. cor. in mound of Earth with charred stake, pits &c as per instructions.
79.80	The corner to Secs. 11, 12, 13 & 14. Land, gently rolling. Soil, 1st rate. Very fine grass.
	North between Secs. 11 & 12. Var. 20° E
20.00	Ravine bears West.
40.00	Set post for $\frac{1}{4}$ Sec. cor. in mound of Earth with charred stake, pits &c as per instructions.
80.00	Set post for corner to Secs. 1, 2, 11 & 12 in mound of Earth with charred stake, pits &c as per instructions. Land, level. Soil, 1st rate.
	East on a random line between Secs. 1 & 12.
40.00	Set post for temporary qr. Sec. cor.
80.30	Intersect East boundary at corner to Secs. 1 & 12 from which I run West on a true line between Secs. 1 & 12.
40.15	Set post for $\frac{1}{4}$ Sec. cor in mound of Earth with charred stake, pits &c as per instructions.
80.30	The corner to Secs. 1, 2, 11 & 12. Land, level. Soil, 1st rate.
	North on a random line between Secs 1 & 2. Var. 20° E.
40.00	Set post for temporary $\frac{1}{4}$ Sec. cor.
80.60	Intersect North boundary 70 lks. West of corner to Secs. 1 & 2 from which I run S. 0°30' W. on a true line between Secs. 1 & 2.