

Subdivision Lines of Township 3 North, Range 32 E. W. M.

Chains 80.00	<p>Set post for corner to Secs. 10, 11, 14 &amp; 15 in mound of Earth with charred stake, pits &amp;c as per instructions.</p> <p>Land, level.</p> <p>Soil, 1st rate.</p> <hr/> <p>East on a random line between Secs. 11 &amp; 14.</p>
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.85	Intersect N. & S. line at corner to Secs. 11, 12, 13 & 14. from which corner I run West on a true line between Secs. 11 & 14.
22.00	Ravine bears S. W..
39.92	Set post for $\frac{1}{4}$ Sec. cor. in mound of Earth with charred stake, pits &c as per instructions.
79.85	<p>The corner to Secs. 10, 11, 14 &amp; 15.</p> <p>Land, level.</p> <p>Soil, good 2nd rate.</p> <hr/> <p>North between Secs. 10 &amp; 11.</p> <p style="text-align: center;">Var. <math>20\frac{1}{4}^{\circ}</math> E.</p>
40.00	Set post for $\frac{1}{4}$ Sec. cor. in mound of Earth with charred stake, pits &c as per instructions
80.00	<p>Set post for corner to Secs. 2, 3, 10 &amp; 11. in mound of Earth with charred stake, pits &amp;c as per instructions</p> <p>Land, level.</p> <p>Soil, good 2nd rate.</p> <hr/> <p>East on a random line between Secs. 2 &amp; 11.</p>
40.00	Set post temporary $\frac{1}{4}$ Sec. cor.
79.50	Intersect N. & S. line at corner to Secs. 1, 2, 11 & 12 from which corner I run West on a true line between Secs. 2 & 11.
39.75	Set post for $\frac{1}{4}$ Sec. cor. in mound of Earth with charred stake, pits &c as per instructions.
79.50	<p>The corner to Secs. 2, 3, 10 &amp; 11.</p> <p>Land, level.</p> <p>Soil, good 2nd rate.</p>