

Subdivision Lines of Township 3 North, Range 32 E. W. M.

Chains	
25.00	Ravine bears West.
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of Earth with charred stake, pits &c as per instructions.
80.00	Set Stone 16x12x4 for corner to Secs. 9, 10, 15 & 16. Land rolling. Soil, 2nd rate.
East on a random line between Secs. 10 & 15.	
40.00	Set post for temporary $\frac{1}{4}$ Sec. corner.
80.10	Intersect N. & S. line at corner to Secs. 10, 11, 14 & 15 from which corner I run West on a true line between Secs. 10 & 15.
40.05	Set post for $\frac{1}{4}$ sec. corner in mound of Earth with charred stake, pits &c as per instructions.
80.10	The corner to Secs. 9, 10, 15 & 16. Land, gently rolling. Soil, 2nd rate.
North between Secs. 9 & 10. Var. 20° E.	
40.00	Set post for $\frac{1}{4}$ sec. cor. in mound of Earth with charred stake, pits &c as per instructions.
80.00	Set post for corner to Secs. 3, 4, 9 & 10 in mound of Earth with charred stake, pits &c as per instructions. Land, gently rolling. Soil, good 2nd rate.
East on a random line between Secs. 3 & 10.	
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.
80.00	Intersect N. & S. line 28 lks. South of corner to Secs. 2, 3, 10 & 11 from which I run S. 89°48' W. on a true line between Secs. 3 & 10.
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of Earth with charred stake, pits &c as per instructions.
80.00	The corner to Secs. 3, 4, 9 & 10. Land, gently rolling. Soil, good 2nd rate; very heavy growth of grass.