

Subdivision Lines of Township 3 North, Range 32 E. W. M.

Chains	<p>stake, pits &c as per instructions.</p>
80.20	<p>The corner to Secs. 5, 6, 7 & 8.</p> <p>Land, rolling.</p> <p>Soil, 2nd rate.</p>
	<p>West on a random line between Secs. 6 & 7.</p>
40.00	<p>Set post for temporary $\frac{1}{4}$ sec. corner.</p>
83.70	<p>Intersect West boundary 60 lks. South of corner to Secs. 6 & 7 from which corner I run</p> <p>S. 89°34' E. on a true line between Secs. 6 & 7.</p>
43.70	<p>Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.</p>
83.70	<p>The corner to Secs. 5, 6, 7 & 8.</p> <p>Land, rolling.</p> <p>Soil, 2nd rate.</p>
	<p>North on a random line between Secs. 5 & 6.</p> <p style="text-align: center;">Var. 20° E.</p>
40.00	<p>Set post for temporary $\frac{1}{4}$ sec. corner.</p>
80.70	<p>Intersect North boundary at corner to Secs. 5 & 6 from which corner I run</p> <p>South on a true line between Secs. 5 & 6.</p>
40.75	<p>Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.</p>
80.75	<p>The corner to Secs. 5, 6, 7 & 8.</p> <p>Land, rolling</p> <p>Soil, good 2nd rate.</p>
	<p>General Description</p>
	<p>The land in this Township is generally either level or gently rolling and covered with a heavy growth of grass. There are but very few springs and no streams of water, and not a tree in the Township.</p> <p>This is the best Township for grass in this section of country.</p>