

East Boundary of Township 3 North, Range 33 E. W. M.

Chains 80.00	<p>Set post for corner to Secs. 12, 13, 7 & 18 in mound of earth with charred stake, pits, trench &c as per instructions.</p> <p>Land, rolling.</p> <p>Soil, 2nd rate.</p>
<p>North on East boundary of Sec. 12.</p> <p style="text-align: right;">Variation 20°30' East.</p>	
40.00	<p>Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits, trench &c as per instructions.</p>
80.00	<p>Set post for corner to Secs. 6, 7, 1 & 12 in mound of earth with charred stake, pits, trench &c as per instructions.</p> <p>Land, gently rolling.</p> <p>Soil, good 2nd rate.</p>
<p>North on East boundary of Sec. 1.</p> <p style="text-align: right;">Variation 20°30' East.</p>	
40.00	<p>Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits, trench &c as per instructions.</p>
80.00	<p>Set post for corner to Townships 3 & 4, North, Ranges 33 & 34 East in mound of earth with charred stake, pits, trench &c as per instructions.</p> <p>Land, gently rolling.</p> <p>Soil, 2nd rate.</p>
<p>From the corner to Townships 3 & 4 North, Ranges 33 & 34 East I run a random line West between said Townships. I set temporary half mile and mile posts at 40.00 and 80.00 chains.</p> <p>I find the Township line to be 5 miles 76 chains and 42 lks. and intersect at township corner.</p>	
<p style="text-align: center;">North Boundary</p> <p>From the corner to Townships 3 & 4 North, Ranges 32 & 33 I run</p> <p>East on North boundary of Sec. 6.</p> <p style="text-align: right;">Variation 20°30' East.</p>	