

Subdivisions of Township 3 North, Range 33 E. W. M.

Chains	Soil, 2nd rate.
	<p>North between Secs. 10 & 11.</p> <p style="text-align: right;">Var. $20\frac{1}{2}^{\circ}$ East.</p> <p>40.00 Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.</p> <p>80.00 Set post for corner to Secs. 2, 3, 10 & 11 in mound of earth with charred stake, pits &c as per instructions.</p> <p>Land, level.</p> <p>Soil, good 2nd rate.</p>
	<p>East on a random line between Secs. 2 & 11.</p> <p>40.00 Set post for temporary $\frac{1}{4}$ sec. corner.</p> <p>80.20 Intersect N. & S. line 34 lks. North of corner to Secs. 1, 2, 11 & 12 from which corner I run</p> <p>N. $89^{\circ}45'$ W. on a true line between Secs. 2 & 11.</p> <p>40.10 Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.</p> <p>80.20 The corner to Secs. 2, 3, 10 & 11.</p> <p>Land, level.</p> <p>Soil, 2nd rate.</p>
	<p>North between Secs. 2 & 3.</p> <p style="text-align: right;">Var. $20\frac{1}{4}^{\circ}$ E.</p> <p>40.00 Set post for temporary $\frac{1}{4}$ sec. cor.</p> <p>79.70 Intersect North boundary 74 lks. East of corner to Secs. 2 & 3 from which I run</p> <p>S. $0^{\circ}32'$ E. on a true line between Secs. 2 & 3.</p> <p>39.70 Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions</p> <p>69.00 Umatilla & Walla Walla road bears NE. & SW.</p> <p>79.70 The corner to Secs. 2, 3, 10 & 11.</p> <p>Land, gently rolling.</p> <p>Soil, 2nd rate.</p>
	<p>North between Secs. 33 & 34.</p> <p>40.00 Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred</p>