

Subdivisions of Township 3 North, Range 33 E. W. M.

Chains		
24.00	Ascend hill.	
35.00	Top of hill.	-200
40.00	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.	C
80.00	Set post for corner to Secs. 15, 16, 21 & 22 in mound of earth with charred stake, pits &c as per instructions. Land, rough & broken. Soil, 2nd rate.	
East on a random line between Secs. 15 & 22.		
40.00	Set temporary $\frac{1}{4}$ sec. cor.	
80.15	Intersect N. & S. line 24 lks. North of corner to Secs. 14, 15, 22 & 23 from which corner I run N. 89°50' W. on a true line between Secs. 15 & 22.	
40.08	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.	C
80.15	The corner to Secs. 15, 16, 21 & 22. Land, rolling. Soil, good 2nd rate.	
North between Secs. 15 & 16.		
Var. 20 $\frac{1}{4}$ ° E.		
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.	
80.00	Set post for corner to Secs. 9, 10, 15 & 16 in mound of earth with charred stake, pits &c as per instructions. Land, level. Soil, 1st rate.	
East on a random line between Secs. 10 & 15.		
40.00	Set temporary $\frac{1}{4}$ sec. cor.	C
80.09	Intersect N. & S. line 18 lks. North of corner to Secs. 10, 11, 14 & 15 from which I run N. 89°52' W. on a true line between Secs. 10 & 15.	
40.04	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.	
80.09	The corner to Secs. 9, 10, 15 & 16.	