

Subdivisions of Township 3 North, Range 33 East W. M.

Chains	
80.00	Set post for corner to Secs. 17, 18, 19 & 20 in mound of earth with charred stake, pits &c as per instructions. Land, gently rolling. Soil, good 2nd rate.
	East on a random line between Secs. 17 & 20.
40.00	Set temporary $\frac{1}{4}$ sec. corner.
80.40	Intersect N. & S. line 36 lks. North of corner to Secs. 16, 17, 20 & 21 from which I run N. 89°45' W. on a true line between Secs. 17 & 20.
40.20	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
80.40	The corner to Secs. 17, 18, 19 & 20. Land, level. Soil, good 2nd rate.
	West on a random line between Secs. 18 & 19.
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.
78.70	Intersect West boundary at corner to Secs. 18 & 19 from which corner I run East on a true line between Secs. 18 & 19.
26.00	Walla Walla & Umatilla Road bears NE. & SW.
38.70	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with pits charred stake &c as per instructions.
78.70	The corner to Secs. 17, 18, 19 & 20. Land, level. Soil, good 2nd rate.
	North between Secs. 17 & 18. Var. 20° East.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
51.00	Road bears NE. & SW.
80.00	Set post for corner to Secs. 7, 8, 17 & 18 in mound of earth with charred stake, pits &c as per instructions. Land, rolling. Soil, good 2nd rate.