

Subdivisional Lines of Township No. 3 North, Range 33 E. W.M.

Chains 79.84	Intersected N. & S. line 14 lks. S. of cor. S. 89°54' W. on true line.
39.92	Set stone 17x14x9 for $\frac{1}{4}$ S. cor.
79.84	To corner. Land, rolling. Good, soil
21.14	North bet. Secs. 21 & 22. To Wild Horse Ck., the Boundary of Reservation.
36.40	West bet. Secs. 21 & 28. To Wild Horse Ck., the Boundary of Reservation.
40.00	North bet. Secs. 32 & 33. Set post and make earth mound for $\frac{1}{4}$ S. cor.
80.00	Set stone 17x10x9 for cor. to Secs. 32, 33, 28 & 29. Land, level. Good soil; good grass.
40.00	East on random bet. Secs. 28 & 33. V. 20°15' E. Set temporary $\frac{1}{4}$ sec. cor.
80.40	Intersected N. & S. line at cor. W. on true line.
40.20	Set stone 14x14x7 for $\frac{1}{4}$ S. cor.
80.40	To corner. Land, generally level. Soil, good.
28.75	North bet. Secs. 28 & 29. To Wild Horse Ck., the Boundary of the Reservation.
40.00	West bet. Secs. 29 & 32. Set stone 20x10x6 for $\frac{1}{4}$ S. cor.
57.10	To Wild Horse Ck., the Boundary of the Reservation.
	North bet. Secs. 31 & 32.