

Subdivisions of T. 3 North, R. 33 East

Chains	
78.75	<p>base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on N. face.</p> <p>Cor. to Secs. 25, 26, 35 and 36.</p> <p>Land, level. Soil, 1st rate. Not cultivated.</p> <p>No timber. Poor grass.</p>
40.00	<p>South on true line bet. Secs. 35 and 36.</p> <p style="text-align: center;">Va. 20° East.</p> <p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor., dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist., raised md. of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ½ ins. square, 12 ins. in the ground, marked 1/16 on W. face.</p>
26.00	Wagon road, E. and W.
40.00	<p>Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for ¼ sec. cor., dug pits 18x18x12 ins. N. and S. of post, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base around it and marked post ¼ S on W. face.</p>
60.00	<p>Set basalt stone 10x10x10 ins., 7 ins. in the ground for 1/16 sec. cor., marked 1/16 W. face, and raised mound of stone 1½ ft. high, 3½ ft. base over it. Pits impractical.</p>
79.28	<p>Intersect S. bdy., Township 110 lks. E. of cor. to Secs. 1 and 2, T. 2 N., R. 33 East, and set charred stake 12 ins. in the ground for closing corner to Secs. 35 and 36, dug pits 18x18x12 ins. NE. and W. of stake, 5½ ft. dist., raised mound of earth 2 ft. high, 4½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked CCC T 3 N R 33 E on N., Sec. 36 on E. and S 35 on W. faces, with 1 notch on E. and 5 notches on West. edges.</p> <p>Land, slightly rolling.</p> <p>Soil, sandy 1st rate. Not cultivated.</p>