

Subdivisions of T. 3 North, R. 33 East

Chains	<p>ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins in the ground, marked $\frac{1}{4}$ S on N. face.</p>
79.70	<p>Cor. to Secs. 26, 27, 34 and 35. Land, level. Soil, 1st rate. Not cultivated. No timber. Poor grass. Aug. 15th 1887</p>
40.00	<p>South on true line bet. Secs. 34 and 35. Var. 20° East. Deposited charred stake 12 in. in the ground for $\frac{1}{4}$ sec. cor., dug pits 18x18x12 ins. N. and S. of stake, $5\frac{1}{2}$ ft. dist., and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S on W. face.</p>
80.00	<p>Intersect S. bdy., of Township 140 lks. E. of cor. to Secs. 2 and 3, T. 2 N., R. 33 E. And deposited charred stake 12 ins. in the ground for closing cor. to Secs. 34 and 35, dug pits 18x18x12 NE. and W. of stake $5\frac{1}{2}$ ft. dist., raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked C C T 3 N on N., R 33 E S 35 on E., and S 34 on W. faces, with 2 notches on E. and 4 notches on W. edges. Land, level. Soil good. Not cultivated. No timber, grass.</p>
18.80	<p>Then commencing at $\frac{1}{4}$ sec. cor. bet. Secs. 21 and 22 which is a stone 9x8x7 ins. buried in the ground, marked $\frac{1}{4}$ S on W. face and mound of stone over it. I run South on a true line bet. Secs. 21 and 22. Va. 21° East. Set basalt stone 12x10x10 ins., 8 ins. in the ground for Meander cor. to fractional Secs. 21 and 22, marked</p>