

Subdivisions of T. 3 North, R. 33 East

Chains	<p>U R M C on S. face, dug a pit 3 ft. square, 1 ft. deep, 8 lks. N. of stone, and raised mound of earth 2 ft. high, <math>4\frac{1}{2}</math> ft. base over it.</p>
24.75	<p>O.R. and N. Railway SW. on bank of Wild Horse creek, SW. Ascend</p>
40.00	<p>Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to Secs. 21, 22, 27 and 28, marked T 3 N S 22 on NE., R 33 E S 27 on SE., S 28 on SW., and S 21 on NW. faces, with 2 notches on S. and 3 notches on E. edges, dug pits 18x18x12 ins. in each sec., <math>5\frac{1}{2}</math> ft. dist., and raised mound of earth 2 ft. high, <math>4\frac{1}{2}</math> ft. base around it.</p> <p>Land, rolling.</p> <p>Soil, 1st. rate. No timber. Some grass.</p>
<p>East on random bet. Secs. 22 and 27.</p>	
<p>Va. 20° East.</p>	
40.00	<p>Set temporary <math>\frac{1}{4}</math> sec. cor. and at</p>
79.37	<p>Intersect N. and S. line 65 lks. S. of cor. to Secs. 22, 23, 26 and 27. Thence S. 89°32' W. on true line.</p>
<p>Va. same</p>	
15.00	<p>Canyon, course N.</p>
17.50	<p>Wagon road, course NE.</p>
39.68	<p>Set basalt stone 10x8x6 ins., 6 ins. in the ground for <math>\frac{1}{4}</math> sec. cor., dug pits 18x18x12 ins. E. and W. of stone, <math>5\frac{1}{2}</math> ft. dist., raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it.</p>
55.00	<p>Gulch and road N.</p>
57.50	<p>Wagon road N.</p>
79.37	<p>Cor. to Secs. 21, 22, 27 and 28.</p>
<p>Land, rolling.</p> <p>Soil, 2nd rate. Some alkaline. Not cultivated.</p> <p>No timber. Scattering sage brush.</p>	
<p>West on random bet. Secs. 21 and 28.</p>	
<p>Va. 20° East.</p>	