

Subdivisions of T. 3 North, R. 33 East

Chains	2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S. on W. face.	
77.50	Canyon E.	-100
79.50	<p>Intersect S. bdy., Township 195 lks. E. of cor. to Secs. 3 and 4, T. 2 N., R. 33 E. and deposited charred stake 12 ins. in the ground for closing cor. to Secs. 33 and 34, dug pits 18x18x12 ins. NE. and W. of cor., $5\frac{1}{2}$ ft. dist., raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked C C T 3 N on N., R 33 E S 34 on E., and S 33 on W. faces with 3 notches on E. and W. edges.</p> <p>Land mostly level.</p> <p>Soil, 1st rate. No timber. Poor grass.</p>	
	<p>South bet. Secs. 28 and 29.</p> <p style="text-align: center;">Va. 20° East.</p> <p>Commencing at cor. to Secs. 20, 21, 28 and 29, which is a stone 6x8x10 ins. above ground, still standing in mound of stone; notches have worn away.</p> <p>Descend.</p>	
20.00	Creek bottom, course E. and W.	
38.90	O.R. and N. Railway and leave field, course SW.	
40.00	<p>Not finding any trace of old $\frac{1}{4}$ sec. cor. I set post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ sec. cor., dug pits 18x18x12 ins. N. and S. of post, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around it and marked post $\frac{1}{4}$ S. on W. face.</p>	
41.25	<p>Set post 4 ft. long, 4 ins. square, 24 ins. in the ground on S. bank of Wild Horse creek for Meander cor. to fractional Secs. 28 and 29, marked MCC U R with T 3 N on S., R 33 E S 28 on E., and S 29 on W faces, and dug a pit 3 ft. square, 12 ins. deep, 8 lks. S. of post and raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base around it.</p>	
62.00	Top of ridge NW.	+150