

Subdivisions of T. 3 North, R. 33 East

Chains	<p>2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S. on W. face.</p>
62.00	Pendleton & Centerville Wagon road, NE. & SW.
80.00	<p>Intersect S. bdy., Township 230 lks. E. of cor. to Secs. 4 and 5, T. 2 N., R. 33 E. and set post 4 ft. long, 4 ins. square, 24 ins in the ground for closing cor. to Secs. 32 and 33, marked C U T 3 N R 33 E on N., S 33 on E., and S 32 on W. faces, with 4 notches on E. and 2 notches on W. edges; dug pits 18x18x12 ins. NE. and W. of post, $5\frac{1}{2}$ ft. dist., raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base around it.</p> <p>Land, rolling.</p> <p>Soil, 1st rate. Not cultivated.</p> <p>No timber. Short grass</p>
	<p>Commencing at cor. to Secs. 29,30, 31 and 32, which is a stone 20x10x8 ins. said to have been replaced at exact cor. point by settlers, old cor. having decayed. I run East on random bet. Secs. 29 and 32.</p> <p style="text-align: center;">Va. 20° East.</p>
40.00	Set temp. $\frac{1}{4}$ sec. cor. and at
79.20	<p>Intersect N. and S. line 50 lks. S. of cor. to Secs. 28, 29, 32 and 33. Thence</p> <p>S. 89°39' W. on true line.</p> <p style="text-align: center;">Va. 21° East.</p>
39.60	<p>Set stone 9x8x7 ins. 6 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face, dug pits 18x18x12 ins. E. and W. of stone, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p>
51.20	Fence SW. and enter field.
53.70	O.R. and N. R. R., SW.
56.30	<p>Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for Meander cor. to fractional Secs. 29 and 32, marked M C U R with T 3 N on E., R 33 E S 29 on N., and S 32 on S. faces, dug a pit 3 ft. square, 1 ft. deep, 8 lks. E. of post, raised mound of earth 2 ft. high, $4\frac{1}{2}$</p>