

Subdivisions of T. 3 North, R. 33 East

Chains	<p>No timber.</p> <p>Short grass. Aug. 16th 1887</p>
	<p>General Description</p> <p>This township is mostly level, excepting parts along the Wild Horse creek and Umatilla river, which is rolling. The soil is first rate. No timber. Grass, short.</p>
	<p>Survey of the Sub-Subdivisional lines of Township 3 North, Range 33 East Willamette Meridian, in the state of Oregon, by James P. Currin and James E. Noland under their joint special contract.</p> <p>Commenced the survey of the Sub-Subdivisional lines of this Township on Oct. 26, 1887.</p>
	<p>East on random through S. $\frac{1}{2}$ of Sec. 36, T. 3 North, R. 33 East.</p> <p style="text-align: center;">Va. 20° East.</p> <p>Commencing at 1/16 sec. cor. 20 chains S. of $\frac{1}{4}$ sec. cor. bet. Secs. 35 and 36. Thence</p> <p>East, setting temporary cors. at 20.40 and 60 chains and at</p>
78.90	<p>Intersect E. bdy. 60 lks. S. of 1/16 sec. cor. Thence S.89°34' W. on true line.</p>
19.72	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor., dug pits 18x18x12 ins. E. and W. of stake, 5$\frac{1}{2}$ ft. dist., raised mound earth 1$\frac{1}{2}$ ft. high, drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
35.50	<p>Wagon road bears N. and S.</p>
39.00	<p>Wagon road bears NE. and SW.</p>
39.45	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor., dug pits 18x18x12 ins. E. and W. of stake, 5$\frac{1}{2}$ ft. dist., raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>