

Examination of Corners of T. 3 North, R. 33 East

Chains

filled & md. washed away.

Found meander cor. between Secs. 22 & 23, a basalt stone, 14x10x5 ins. firmly set in the ground, marked U R M C on S. face with 3 ft. square pit 8 lks. S. nearly full & E. md. gone by overflow of creeks.

Found meander cor. between Secs. 23 & 24, a basalt stone, 18x10x8 ins. firmly set in the ground. Pit & earth mound nearly obliterated by overflow of creek. The stone is marked U R M C on S. face.

Found cor. to Secs. 23, 24, 25 & 26, a post 4 ins. sq., 2 ft. above ground, marked S 24 T 3 N on NE., S 25 R 33 E on SE., S 26 on SW., & S 23 on NW. faces. Pits, 5½ ft. dist. in each sec. with mound of earth almost obliterated by stock. Notches gone. I out 2 on S. & 1 on E. edges.

Cor. to Secs 25, 26, 35 & 36 I find to be a post, 4 ft. long by 4 ins. square, lying down, marked S 25 T 3 N on NE., S 36 R 33 E D R on SE., S 35 on SW. & S 26 on NW. faces. Pits partly filled. Mound almost gone. I reset posts and cut 1 notch on E. & S. edges of it.

Resurvey of Subdivisions of Township 3 North, Range 33 East Willamette Meridian, in the state of Oregon, by James P. Currin and James E. Noland under their special contract, dated May 4, 1887

Beginning at cor., Secs. 29, 30, 31 & 32, which is a decayed post 18 ins. long by 3 ins. square above ground, marked S 23 T 3 N on NE., S 32 R 33 E on SE., S 31 on SW., & S 30 on NW. faces with a mound of stone around it. South bet. Secs. 31 & 32.

Var. 20° E.

- 7.00 O. & W. T. R. R. course NE. & SW. New line.
- 12.20 R. & W. W. R. R. course NE. & SW.
- 22.40 Could find no trace of meander cor.
- 24.50 Wild Horse Creek, 15 lks., runs SW.
- 29.60 A Road. Course NE.
- 32.00 Top of Hill, NE.

4100  
ft.