

Resurvey of Subdivisions, T. 3 North, R. 33 East

Chains	
39.00	Canon, course NE. .
40.00	All trace of $\frac{1}{4}$ cor. destroyed by badgers & stock.
79.36	To closing cor., Secs. 31 & 32, which is a post 4 ft. long x 4 ins. squared, marked C C T.3 N R 33 E on N., S 32 on E. face & S 31 on W. face and D R on S. face with 5 notches on E. & 1 on W. edges. Pits at E. & W., $5\frac{1}{2}$ ft. dist., in good state of preservation. Md. of earth partly blown away. This cor. is 390 lks. East of cor. to Secs. 5 & 6. The mistake was in copying notes.
	From cor. to Secs. 29, 30, 31 & 32
	N. 89°39' E. bet. Secs. 29 & 32.
	Var. 20° E.
15.75	O. & W. T. R. R., course NE. & SW..
22.85	Wild Horse Creek, course SW. 15 lks.
22.85	Meander cor. bet. 29 & 32 standing, a post 2 ft. long by 4 ins. square above ground. Marked U R M C on E. face, S 29 on N. face, S 32 on S. face; stone md. around it.
39.50	To $\frac{1}{4}$ sec. cor. a stone 9x5x7 is set firmly in the ground, marked $\frac{1}{4}$ on N. face. Pits E. & W., $5\frac{1}{2}$ ft. dist., which are partly filled. E. md. partly good.
79.01	To cor. Secs. 28, 29, 32 & 33, which I find to be a stone, 15x10x3, firmly set in the ground with 4 notches on E. & 1 on S. edges. I set a post 4 ft. long, 4 ins. square, marked S 28 T 3 N on NE., S 32 R 33 E on SE., S 32 on SW., & S 29 on NW. faces, with 4 notches on E. & 1 on S. edges. Set the post 2 ft. in ground by side of stone. The pits are $5\frac{1}{2}$ ft. dist. in each sec. in good repair. Earth mound, partly blown away.
	From the corner to Secs. 28, 29, 32 & 33 I run thence S. bet. Secs. 32 & 33.
	Var. 21° E.
17.00	Gulch & road, course SE.
40.00	To a point 60 lks. W. of $\frac{1}{4}$ sec. cor. I moved it to this point & reset it by setting the charred stake 12 ins.