

Resurvey of Subdivisions, T. 3 North, R. 33 East

Chains	
66.20	Enter Pendleton & Adams Road, NE.
68.20	Leave Pendleton & Adams Road, NE.
80.00	Intersect S. bdy., 120 links W. of closing cor. & 2.30 lks. E of cor. Secs. 4 & 5, moved closing cor. to this point & reset it. Deposited charred stake, post being gone, supplied a post 4 ft. long, by 4 ins. square, 2 ft. in ground, marked C C T 3 N R 33 E on N. face & S 33 on E face, S 32 on W. face, and D R on S. face. Cut 4 notches on E., & 2 on W. edges. Dug pits 18x18-x12, E. N. & W., 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base around it.