

Survey of South Boundary of Township No. 4 North, Range 34 East Willamette Meridian in the state of Oregon, by William H. Odell, deputy Surveyor, under contract No. 110, bearing date, February 7th 1865.

Chains	
	<p>West on random on South boundary of Township No. 4 N.,  R. 34 E. April 25th 1865.  V. 21°30' E.</p> <p>Set temporary mile &amp; half mile posts at 80. &amp; 40. chs.  481.40. Intersect East boundary of Township No. 3  N., R. 33 East of Willa. Mer. 12.60 South of NE. corner.  I found April 29th the exterior line of Township No.  4 N., R. 33 E. to be 469.33 chs., hence 10.67 chs.  short. I, therefore correct South boundary by start-  ing 10.67 South of North East corner of Township No.  3 N., R. 33 E. Thence East course.</p>
	<p>S. 89°48' East. Var. 20°30' E.</p>
41.40	Set $\frac{1}{4}$ section post on level. Drove charred stake, dug pits and raised mound as per instructions.
81.40	Set post corner for sections 5, 6, 31 & 36 on level. Drove charred stake, dug pits and raised mound as per instructions.
	<p>Land, gently rolling.  Good grass, soil 2nd rate.</p>
	<p>S. 89°48' E. on North boundary of section 32 T. 4 N.,  R. 34 E. Va. 20°30' E.</p>
40.00	Set $\frac{1}{4}$ section post. Drove charred stake, dug pits, and raised mound as per instructions.
80.00	Set post corner for sections 4, 5, 32 & 33. Drove charred stake, dug pits and raised mound as per instructions.
	<p>Land rolling, good grass.  Soil, good 2nd rate.</p>
	<p>S. 89°48' E. on south boundary of section 33, T. 4 N.,  R. 34 E. Var. 21°30' E.</p>
40.00	Set $\frac{1}{4}$ section post corner. Drove charred stake, dug pits raised mound as per instructions.