

Township No. 3 North, Range 35 East W. M.

Chains	Land, gently rolling prairie. Good grass. Soil, 2nd rate.	
40.00 80.00	South on West boundary of Section 30. Var. 21° East. Set $\frac{1}{4}$ section post corner, drove charred stake, dug pits and raised mound as per instructions. Set post corner for Sections 30, 31, 25 & 26, Drove charred stake, dug pits, and raised mound as per instructions. Land, rolling prairie. Good grass. Soil, 2nd rate.	-10
20.00 40.00 80.00	South on West boundary of Section 31. Var. 22° East. Begin to descent toward the Umatilla River. Set $\frac{1}{4}$ section post corner. Drove charred stake, dug pits and raised mound as per instructions. Set post corner for sections 31, 6, 1 & 36, Ts. 2 & 3 N., Rs. 34 & 35 East, on steep hill side facing the South. Drove charred stake and raised stone mound as per instructions. Land, broken. Good grass. Soil, 2nd rate.	-30 -150
40.00 43.50	Survey of the Subdivision lines of Township number 3, North of the base line of Range 34 East of W. M. by William H. Odell, deputy surveyor, under contract No. 114, bearing date July 2nd 1866.  The greater part of this Township being on the Umatilla Indian Reservation, consequently not subject to survey.  I commence at post corner for sections 2, 3, 34 & 35 on North boundary of Township. Thence South between Sections 2 & 3. Set post corner for $\frac{1}{4}$ section. Drove charred stake, dug pits and raised mound as per instructions. Spring branch 3 lks. wide, course NW.	