

Survey of the Subdivisional Lines of Township No. 3 North of Range No. 34, East of the Will. Mer. by Z. F. Moody, under contract No. 164, bearing date Oct. 4, 1871

Chains	North bet. Secs. 35 & 36.
40.00	Set post and made earth mound for $\frac{1}{4}$ S. cor.
80.00	Set post and made mound of earth for cor. to Secs. 35, 36, 25 & 26.
	Land, generally rolling.
	Soil, good. First rate grass.
	East on random bet. Secs. 25 & 36.
	V. 20° E.
40.00	Set temporary $\frac{1}{4}$ sec. corner.
80.14	Intersected N. & S. line 22 lks. S. of cor.
	S. 89°51' W. on true line.
40.07	Set stone 14x12x7 for $\frac{1}{4}$ S. cor.
80.14	To corner.
	Land, generally rolling.
	Soil, good. Grass, good.
	North bet. Secs. 25 & 26.
40.00	Set post and made earth mound for $\frac{1}{4}$ sec. corner.
80.00	Set post and made earth mound for cor. to Secs. 25, 26, 23 & 24.
	Land, rolling.
	Soil, good. Good grass.
	East on random bet. Secs. 24 & 25.
	V. 21° E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
79.90	Intersected N. & S. line at cor.
	W. on true line.
39.95	Set stone 14x12x5 for $\frac{1}{4}$ S. cor.
79.90	To corner.
	Land, rolling.
	Soil, good. Good grass.
	North bet. Secs. 23 & 24.
13.00	Cayuse & Walla Walla Road, NE.
40.00	Post and earth mound for $\frac{1}{4}$ S. cor.
80.00	Set post and made earth mound for cor. to Secs. 23, 24,