

Subdivisional Lines of Township 3 North, R. 34 E. W. M.

Chains	Soil, 1st rate. Good Grass	Oct. 27, 1871.
	North bet. Secs. 33 & 34.	
40.00	Set post and made mound of earth for $\frac{1}{4}$ sec. cor.	
80.00	Set post and made mound of earth for cor. to Secs. 33, 34, 27, 28.	
	Land, rolling. Soil, 1st rate.	
	East on random bet. Secs. 27 & 34.	
	V. 20° E.	
40.00	Set temporary $\frac{1}{4}$ S. cor.	
80.12	Intersected N. & S. line 14 lks. S. of cor. S. 89°54' W. on true line.	
24.00	Road NE. & SW.	
40.06	Set post and made earth mound for $\frac{1}{4}$ S. cor.	
80.12	To corner. Land, generally level. Good grass. Soil, 1st rate.	
	North bet. Secs. 27 & 28.	
40.00	Set post and made mound of earth for $\frac{1}{4}$ sec. corner.	
80.00	Set post and made earth mound for cor. to Secs. 27, 28, 21 & 22.	
	Land, rolling. Good grass. Soil, good.	
	East on random bet. Secs. 22 & 27.	
	V. 20° E.	
40.00	Set temporary $\frac{1}{4}$ S. cor.	
80.10	Intersected N. & S. line 24 lks. N. of cor. N. 89°50' W. on true line.	
40.05	Set post and made mound of earth for $\frac{1}{4}$ S. cor.	
80.10	To corner. Land, level. Good soil	
	North bet. Secs. 21 & 22.	