

Subdivisional Lines of Township 3 North, R. 34 E. W. M.

Chains	
	Soil, good. Good grass.
	East on random bet. Secs. 21 & 28. V. 21° E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.00	Intersected N. & S. line 18 lks. N. of cor. N. 89°52' W. on true line.
40.00	Set post and made mound of earth for $\frac{1}{4}$ sec. cor.
80.00	To cor. Land, rolling. Soil, good.
	North bet. Secs. 21 & 20.
40.00	Set post and made earth mound for $\frac{1}{4}$ sec. cor.
80.00	Set post and made mound of earth for cor. to Secs. 21, 20, 16 & 17. Land, rolling. Soil, good. Oct. 28, 1871
	East on random bet. Secs. 16 & 21. V. 20°30' E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.20	Intersected N. & S. line 16 lks. S. of cor. S. 89°53' W. on true line.
40.10	Set post and made mound of earth for $\frac{1}{4}$ sec. cor.
80.20	To corner. Land, rolling. Soil, good. Good grass.
	North bet. Secs. 16 & 17.
40.00	Set post and made earth mound for $\frac{1}{4}$ S. cor.
44.50	Old wagon road, dim.
80.00	Set post and made earth mound for cor. to Secs. 16, 17, 8 & 9. Land, rolling. Good grass.
	East on random bet. Secs. 9 & 16. V. 21°30' E.