

Subdivisional Lines of Township 3 North, R. 34 E. W. M.

|                 |   |
|-----------------|---|
| Chains<br>79.75 | To corner.<br>Land, rolling.<br>Soil, good.   |
| 40.00<br>57.10  | North bet. Secs. 17 & 18.<br>Set post and made earth mound for $\frac{1}{4}$ sec. cor.<br>To Wild Horse ck., the bdy. of the Reservation.<br>Oct. 30, 1871.<br>Contract No. 165   |
|                 | Exterior lines of T. 4 North, R. 34 E. W. M., as surveyed by James P. Currin & James E. Noland, U. S. Deputy Surveyors, under their special contract, dated May 4th 1887.<br>South Boundary   |
| 13.50           | From cor. to Tps. 3 & 4 N., Rs. 34 & 35 E., I run W. on random bet. Tps. 3 & 4 N.R. 34 E.<br>Var. 19°45' E.<br>I set temporary half mile and mile corners at each 40 & 80 chs. At 3 miles I found the corner to Secs. 3, 4, 33 & 34 to be 40 lks. N. of line.<br>From this cor., which is a post in earth mound & with pits, I run S. 89°54' E. on true line bet. Sec. 3 & 34.<br>Var. 21° E.<br>Intersect U. R. bdy. at meander cor. Set a basalt stone 9x8x7 ins. 6 ins. in the ground for meander cor. to fractional Secs. 3 & 34, marked U R M C. Dug a pit 3 ft. square and 1 ft. deep, 8 lks. E. of cor. and raised a mound of earth 2 ft. high, 4 $\frac{1}{2}$ ft. base along side. |
| 40.00           | Set a post 36x3x3 ins. 12 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ S. on N. face. Dug pits 18x18x12 ins. E. & W. of cor. 5 $\frac{1}{2}$ ft. dist., raised a mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base around post.  |
| 42.75           | Walla Walla branch R. R., course NW.  |
| 44.50           | Wagon Road.   |