

Exterior lines of T. 3 North, R. 34 E. W. M., as surveyed by James P. Currin & James E. Noland, U. S. Deputy Surveyors, under their special contract, dated May 4th 1887.

Chains	Beginning at cor. to Tps. 3 & 4 N., Rs. 34 & 35 E., I run S. on true line bet. Secs. 1 & 6.
	Var. 19°30' E.
1.40	Wagon Road, course SE.
11.75	Wagon Road, course E.
16.00	Wagon Road, course E.
20.00	Deposited a charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. & S. of cor., 5½ ft. dist. and raised a mound of earth 1½ ft. high, 3½ ft. base over it. In N. pit, drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W face.
27.50	Wagon Road, course S. E.
38.00	Wagon Road, course E.
40.00	Set a post 36x3x3 ins. 12 ins. in the ground for ¼ sec. cor., marked ¼ S on W. face. Dug pits 18x18x12 ins. N. & S. of cor., 5½ ft. dist. & raised a mound of earth 1½ ft. high, 3½ ft. base around post.
60.00	Deposited a charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. & S. of post, 5½ ft. dist. and raised a mound of earth 1½ ft. high, 3½ ft. base over it. In N. pit drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 on W. face.
64.40	Wagon Road, course S.
80.00	Set a basalt stone 12x10x8 ins. 8 ins. in the ground for cor. to Secs. 6,7, 1 & 12. Marked 5 notches on S. & 1 notch on N. edges. Dug pits 18x18x12 ins. in each Sec. 5½ ft. dist., raised a mound of earth 2 ft. high, 4½ ft. base alongside.
	Land, rolling. Some grass. Soil, 1st rate.
	South on E. bdy., Sec. 12. Var. 19°30' E.
9.20	Dry ditch, course SE.