

Subdivisions of T. 3 North, R. 34 East W. M.

Chains 20.00	Set stone 20x12x10 18 ins. in the ground for 1/16 sec. cor., marked 1/16 on W. face. Dug pits 18x18x12 ins. N. and S. of stone, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it.
27.00	Creek, NW., 10 lks. wide. Ascend.
40.00	Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it. And in N. pit drove stake 2 ft. long, 2 ins. sq., 12 ins. in the ground, mkd. ¼ S on W. face.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face
76.50	Land, E. and W.
80.00	Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to Secs. 11, 12, 13 and 14, marked T 3 N S 12 on NE., R 34 E S 13 on SE., S 14 on SW., and S 11 on NW., faces with 4 notches on S. and 1 notch on E. edges. Dug pits 18x18x12 ins. in each sec. 5½ ft. dist. Raised mound of earth 2 ft. high, 4½ ft. base over it. Land, rolling. Soil, 1st rate. All cultivated.
79.56	East on random bet. Secs. 12 and 13. Va. 20° East. Set temporary cors. at 20, 40 and 60 chains, and at Intersect E. bdy. Township 35 lks. N. of cor. to Secs. 12, 13, 7 and 18. Thence North 89°45' W. on true line. Va. same.
19.89	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake