

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	
40.00	<p>dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in N. pit drove stake, 2 ft. long, 2 ins. sq., 12 ins. in the ground, marked 1/16 S on W. face.</p> <p>Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in N. pit drove stake, 2 ft. long, 2 ins. sq., 12 ins. in the ground, mkd. $\frac{1}{4}$ S on W. face.</p>
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in N. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.</p>
80.00	<p>Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to Secs. 25, 26, 35 and 36, mkd. T 3 N S 25 on NE., R 34 E S 36 on SE., S 35 on SW. and S 26 on NW. faces and with 1 notch on S. and E. edges. Dug pits 18x18x12 ins. in each sec., $5\frac{1}{2}$ ft. dist. and raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base around it.</p>
	<p>Land, slightly rolling. Soil, 1st rate. Partly cultivated.</p>
	<p>East on ran. bet. Secs. 25 and 36.</p>
	<p>Var. $20\frac{3}{4}^{\circ}$ East.</p>
79.65	<p>Set temporary cors. at 20, 40 and 60 chains, and at Intersect E. bdy. Township 78 lks. N. of cor. to Secs. 25, 36, 30 and 31. Thence. North $89^{\circ}27'$ West on true line. Va. 20° East.</p>
4.90	<p>Leave field, N. and S.</p>
19.91	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake,</p>