

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	<p>for cor. to Secs. 2, 3, 10 & 11, marked T 3 N S 2 on NE., R 34 E S 11 on SE., S 10 on SW., and S 3 on NW. faces, with 5 notches on S. and 2 notches on E. edges. Dug pits 18x18x12 ins. in each sec., 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it. Land, mostly level. Soil, 1st rate. Well adapted to agriculture.</p>
	<p>East on ran. bet. Secs. 2 & 11. Va. 20° East.</p>
79.40	<p>Set temporary cors. at 20, 40 and 60 chains and at Intersect N. and S. line 20 lks. S. of cor. to Secs. 1, 2, 11 and 12. Thence S. 89°51' W. on true line. Va. same.</p>
19.85	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
37.10	<p>Fence N. and S.</p>
39.60	<p>Well, 15 ft. deep in yard.</p>
39.70	<p>Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on N. face, from which A dwelling house bears North about 75 lks.</p>
41.00	<p>Spring branch, N. W., 3 lks. wide.</p>
59.55	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on</p>