

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	<p>N. face.</p> <p>74.75 Fence, N.</p> <p>79.40 Cor. to Secs. 2, 3, 10 and 11.</p> <p>Land, rolling.</p> <p>Soil, 1st & 2nd rate. Partly under cultivation.</p>
20.00	<p>South bet. Secs. 10 and 11.</p> <p style="text-align: center;">Va. 20° East.</p> <p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of cor. 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.</p>
40.00	<p>Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground, marked ¼ S on W. face.</p>
40.60	<p>Gulch, W.</p>
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in N. pit, drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.</p>
73.50	<p>Old Well, dry, 10 ft. deep.</p>
80.00	<p>Deposited charred stake 12 ins. in the ground for cor. to Secs. 10, 11, 14 and 15. Dug pits 18x18x12 ins. in each sec., 5½ ft. dist. Raised mound of earth 2 ft. high, 4½ ft. base over it and in SE. pit, drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked T 3 N S 11 on NE., R 34 E S 14 on SE., S 15 on SW., and S 10 on NW. faces with 4 notches on S and 2 on E. edges.</p>