

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	<p>ft. base over it, and in N. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.</p>
37.00	Leave plowed field.
40.00	<p>Deposited charred stake 12 ins. in the ground on <math>\frac{1}{4}</math> sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, <math>5\frac{1}{2}</math> ft. dist. Raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it, and in N. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked <math>\frac{1}{4}</math> S on West face.</p>
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, <math>5\frac{1}{2}</math> ft. dist. Raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it, and in N. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.</p>
79.00	Wagon road, W.
80.00	<p>Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to Secs. 14, 15, 22 and 23. Dug pits 18x18x12 ins. in each sec., <math>5\frac{1}{2}</math> ft. dist. Raised mound of earth 2 ft. high, <math>4\frac{1}{2}</math> ft. base around post, which is marked T 3 N S 14 on NE., R 34 E S 23 on SE., S 22 on SW., and S 15 on NW. faces, with 3 notches on S. and 2 notches on East edges.</p> <p>Land, level.</p> <p>Soil, 1st rate. Mostly cultivated.</p>
	<p>East on ran. bet. Secs. 14 and 23.</p> <p style="text-align: center;">Va. 20° East.</p>
80.75	<p>Set temporary cors. at 20, 40 and 60 chains and at Intersect N. and S. line 12 lks. S. of cor. to Secs. 13, 14, 23 and 24. Thence</p> <p>S. 89°55' W. on true line.</p>
20.18	Deposited charred stake 12 ins. in the ground for 1/16