

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	S. and 2 notches on E. edges.
	Land, mostly level.
	Soil, 1st rate. Some grass.
	Partly cultivated.
	East on ran. bet. Secs. 26 and 35.
	Va. $20\frac{1}{2}^{\circ}$ E.
80.50	Set temporary cors. at 20, 40 and 60 chains and at Intersect N. and S. line 14 lks. S. of cor. to Secs. 25, 26, 35 and 36. Thence S. $89^{\circ}54'$ West on true line.
	Va. $20\frac{3}{4}^{\circ}$ E.
20.12	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of post, $5\frac{1}{2}$ ft. dist., and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around it.
40.25	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S on N. face.
60.37	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.
63.80	Wagon road NE. and SW.
80.50	Cor. to Secs. 26, 27, 34 and 35.
	Land, gently rolling.
	Soil, 1st rate. Not under cultivation.
	South on ran. bet. Secs. 34 and 35.
	Va. $20\frac{1}{2}^{\circ}$ E.
	Set temporary cors. at 20, 40 and 60 chains and at