

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	East on ran. bet. Secs. 10 and 15.
	Va. 21° East.
	Set temporary cors. at 20, 40 and 60 chains and at
80.20	Intersect N. and S. line 110 lks. N. of cor. to Secs. 10, 11, 14 and 15. Thence N. 89°13' W. on true line.
	Va. 20° East.
.75	Fence and enter field, N. and S.
20.05	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on N. face.
40.10	Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S. on N. face.
41.25	Leave field, N. and S.
60.15	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
80.20	Cor. to Secs. 9, 10, 15 and 16. Land, level. Soil, 1st rate. Partly cultivated.
	South bet. Secs. 15 and 16.
	Va. 21° East.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base