

Subdivisions of T. 3 North, R 34 East W. M.

Chains	
80.00	<p>5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in North pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.</p> <p>Deposited charred stake 12 ins. in the ground for cor. to Secs. 21, 22, 27 and 28. Dug pits 18x18x12 ins. in each sec., 5½ ft. dist. Raised mound 2 ft. high, 4½ ft. base over it and in SE. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked T 3 N S 22 on NE., R 34 E S 27 on SE., S 28 on SW., and S 21 on NW. faces with 2 notches on S and 3 notches on E. edges.</p> <p>Land, rolling.</p> <p>Soil, good. Not under cultivation.</p>
80.40	<p>East on ran. bet. Secs. 22 and 27.</p> <p style="text-align: center;">Va. 20° East.</p> <p>Set temporary sec. cors. at 20, 40 and 60 chs. and at Intersect N. and S. line 75 lks. N. of cor. to Secs. 22, 23, 26 and 27. Thence N. 89°:28' W. on true line.</p>
20.10	<p style="text-align: center;">Va. 20¼° East.</p> <p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
40.20	<p>Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on W. face.</p>
60.30	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake,</p>