

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	Land, rolling. Soil, 1st rate. Not cultivated.	
80.20	East on ran. bet. Secs. 27 and 34. Va. 20° East Set temporary cors. at 20, 40 and 60 chains and at Intersect N. and S. line 63 lks. N. of cor. to Secs. 26, 27, 34 and 35. Thence N. 89°33' W. on true line. Va. 20½° East.	
15.00	Wagon road, NW.	
20.05	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on N. face.	
35.50	Wagon road, N. Ascend sloping hill.	
40.10	Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S. on N. face.	
60.15	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit, drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on N. face.	
80.20	Cor. to Secs. 27, 28, 33 and 34. Land, rolling. Soil, 1st rate. Not cultivated.	+400
	South on ran. bet. Secs. 33 and 34. Va. 20° E.	