

Subdivisions of T. 3 North, R 34 East W. M.

Chains	Set temporary $\frac{1}{4}$ and $1/16$ sec. cors. at 20, 40 and 60 chains and at
79.52	Intersect S. bdy. Township 16 lks. W. of cor. to Secs. 33 and 34. Thence N. 7° W. on true line.
	Va. 21° East.
2.25	Wagon road, E. and W.
19.52	Set stone $10 \times 8 \times 8$ ins. 6 ins. in the ground for $1/16$ sec. cor., marked $1/16$ on W. face. Dug pits $18 \times 18 \times 12$ ins. N. and S. of stone, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
39.52	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor. Dug pits $18 \times 18 \times 12$ ins. N. and S. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S. on W. face.
59.52	Deposited charred stake 12 ins. in the ground for $1/16$ sec. cor. Dug pits $18 \times 18 \times 12$ ins. N. and S. of stake $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $1/16$ S. on W. face.
79.52	Cor. to Secs. 27, 28, 33 and 34. Land, rolling. Soil, 1st rate, same as before.
	Commencing at cor. to Secs. 3, 4, 9 and 10 I run West on random bet. 4 and 9. Va. 20° E.
40.20	A point 146 lks. S. of old $\frac{1}{4}$ sec. cor. which is still standing. Thence S. $87^{\circ}54'$ E. on true line. Va. $19\frac{1}{2}^{\circ}$ East.
20.50	Wild Horse creek SW. 5 lks. wide.
21.70	Set post 4 ft. long, 4 ins. square, 24 ins. in the ground