

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	
40.20	<p>for Meander cor. to fractional Secs. 4 and 9, marked M. C. with T 3 N R 34 E on E., S 4 on N. and S 9 on S. faces. Dug a pit 3 ft. square 1 ft. deep, 8 lks. E. of post and raised mound of earth 2 ft. high, 4½ ft. base around post.</p> <p>Cor. to Secs. 3, 4, 9 and 10. Land, rolling. Soil, 1st rate. Cultivated.</p>
20.10	<p>Commencing at old ¼ sec. cor. bet. Secs. 8 and 9, which is post 3 ft. long, 3 ins. square, 24 ins. in the ground, fairely preserved in old mound with 2 pits. After reestablishing same, I run South on true line bet. Secs. 8 and 9. Va. 21° East.</p> <p>Wild Horse Creek, 5 lks. wide, W.</p>
20.25	<p>Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for Meander cor. to fractional Secs. 8 and 9, marked M.C. with T 3 N on N., R 34 E S 9 on E. S 8 on W. faces, and dug a pit 3 ft. square, 1 ft. deep, 8 lks. S. of post. Raised mound of earth 2 ft. high, 4½ base around it.</p>
39.95	<p>Old mound &amp; pits.</p>
40.00	<p>Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to Secs. 8, 9, 16 and 17, marked T 3 N S 9 on NE., R 34 E S 16 on SE., S 17 on SW., and S 8 on NW. faces, with 4 notches on S. and E. edges. Dug pits 18x18x12 ins. in each sec. 5½ ft. dist. and raised mound of earth 2 ft. high, 4½ ft. base over it.</p> <p>Land, rolling. Soil, 1st rate. Some alkali. Partly cultivated.</p>
80.00	<p>East on ran. bet. Secs. 9 and 16. Va. 21° E. Set temporary cors. at 20, 40 and 60 chains and at Intersect N. and S. line at cor. to Secs. 9, 10, 15 and 16. Thence</p>