

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	
	<p>Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S. on W. face.</p>
45.50	<p>Wagon road, NE.</p>
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.</p>
80.00	<p>Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to Secs. 16, 17, 20 and 21, marked T 3 N S 16 on NE., R 34 E S 21 on SE., S 20 on SW., and S 17 on NW. faces with 3 notches on S. and 4 notches on E. edges. Dug pits 18x18x12 ins. in each sec., 5½ ft. dist. Raised mound of earth 2 ft. high, 4½ ft. base over it.</p> <p>Land, level. Soil, 1st rate.</p> <p>Soil, 1st rate. Not under cultivation.</p>
	<p>East on ran. bet. Secs. 16 and 21.</p> <p style="text-align: center;">Va. 21° East.</p> <p>Set temporary cors. at 20, 40 and 60 chains, and at</p> <p>79.70 Intersect N. and S. line 5 lks. N. of cor. to Secs. 15, 16, 21 and 22. Thence</p> <p>N. 89°58' West on true line.</p> <p style="text-align: center;">Va. 20° East.</p>
.50	<p>Wagon road, NW.</p>
19.92	<p>Set charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W., 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
39.85	<p>Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½</p>