

Subdivisions of T. 3 North, R 34 East W. M.

|        |   |     |
|--------|---|-----|
| Chains | <p>on NE., R 34 E S 28 on SE., S 29 on SW., and S 20 on NW. faces with 2 notches on S and 4 notches on E. edges. Dug pits 18x18x12 ins. in each sec., 5½ ft. dist. Raised mound of earth 2 ft. high, 4½ ft base. around it.</p> <p>Land, level.</p> <p>Soil, 1st rate. Not cultivated.</p>    |     |
|        | <p>East on ran. bet. Secs. 21 and 28.</p> <p style="text-align: center;">Va. 20° East.</p> <p>Set temporary cors. at 20, 40 and 60 chains and at</p>  |     |
| 80.00  | <p>Intersect N. &amp; S. line 23 lks. N. of cor. to Secs. 21, 22, 27 and 28. Thence</p> <p>N. 89°50' W. on true line.</p> <p style="text-align: center;">Va. same.</p>  |     |
| 10.00  | Top of Hill   | +50 |
| 20.00  | <p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p> |     |
| 40.00  | <p>Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on N. face.</p>       |     |
| 60.00  | <p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face</p>   |     |
| 80.00  | <p>Cor. to Secs. 20, 21, 28 and 29.</p> <p>Land, rolling.</p>   |     |