

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	Soil, 1st rate. Not cultivated.
	South bet. Secs. 28 and 29.
	Va. 20° East.
20.00	Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.
40.00	Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on N. face.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.
80.00	Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to Secs. 28, 29, 32 and 33, marked T 3 N S 28 on NE., R 34 E S 33 on SE., S 32 on SW., and S 29 on NW. faces with 1 notch on S. and 4 notches on E. edges. Dug pits 18x18x12 ins. in each sec., 5½ ft. dist. Raised mound of earth 2 ft. high, 4½ ft. base over it.
	Land, level.
	Soil, 1st rate. Not cultivated.
	East on ran. bet. Secs. 28 and 33.
	Va. 20° East.
79.80	Set temporary cor. at 20, 40 and 60 chains and at Intersect N. and S. line at cor. to Secs. 27, 28, 33 and 34. Thence