

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	West on true line.	
	Va. 20° E.	
19.95	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.	
25.25	Wagon road, SW.	
39.90	Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on N. face.	
44.00	Summit of ridge.	+100
59.85	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth, 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.	
79.80	Cor. to Secs. 28, 29, 32 and 33. Land, rolling. Soil, 1st rate. Not cultivated.	
	South on random bet. Secs. 32 and 33. Va. 20° East.	
79.06	Set temporary cors. at 20 and 40 and 60 chains, and at Intersect S. bdy., Township, 30 lks. E. of cor. to Secs. 32 and 33. Thence N. 13' East on true line.	
	Va. 20½° East.	
15.00	Canon, SW.	-200
19.06	Set stone 16x12x8 ins. 9 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stone, 5½	