

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	
39.06	<p>ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{16}$ S on W. face.</p> <p>Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S on W. face.</p>
59.06	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground & marked $\frac{1}{4}$ S on W. face.</p>
65.00	Wagon road, E. and W.
71.00	Wagon road, NW.
79.06	<p>Cor. to Secs. 28, 29, 32 and 33.</p> <p>Land, rolling.</p> <p>Soil, 1st rate. Not cultivated.</p>
40.00	<p>From the corner to Secs. 8, 9, 16 & 17 I run West on ran. bet. Secs. 8 and 17.</p> <p style="text-align: center;">Va. 21° E.</p> <p>A point 102 lks. S of $\frac{1}{4}$ sec. cor. bet. Secs. 8 and 17, which is an old post and charcoal in mound of earth with pits. Thence</p> <p>S.88°33' E. on true line.</p> <p style="text-align: center;">Va. 21° East.</p>
14.80	<p>Set stone 16x10x8 ins. 10 ins. in the ground for Meander cor. to fractional Secs. 8 and 17, marked M.C. with T 2 N on E., R 34 E S 8 on N., S 17 on S. faces, and dug a pit, 3 ft. square, 1 ft. deep, 8 lks. East of stone. Raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over stone.</p>