

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	
14.90	Wild Horse Creek, 10 lks., SW.
18.50	Enter field.
20.00	O. R. & N. Railway, SW.
40.00	Cor. to Secs. 8, 9, 16 and 17. Land, mostly level. Soil, 1st rate. Partly cultivated.
Commencing at cor. to Secs. 7, 8, 17 and 18, which is post, very rotten and has been replaced with a stone 6 ins. square above ground; old pits are still visable and after reestablishing same I run South on true line bet. Secs. 17 and 18. Va. 21° East.	
25.50	O. R. and N. Railway, NE.
31.00	Wild Horse creek, 10 lks. wide. Runs SW.
31.50	Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for Meander cor. to fractional Secs. 17 and 18, marked M.C. with T 3 N on S., R 34 E S 17 on E., and S 18 on W. faces, and dug a pit 3 ft. square, 1 ft. deep, 8 lks. S. of post, and raised mound of earth 2 ft. high, 4½ ft. base around it.
40.00	Deposited marked stone 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. N. and S. of stone, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in N. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on W. face.
80.00	Deposited charred stake 12 ins. in the ground for cor. to Secs. 17, 18, 19 and 20. Dug pits 18x18x12 ins. in each sec., 5½ ft. dist. Raised mound of earth 2 ft. high, 4½ ft. base over it, and in SE. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked T 3 N S 17 on NE., R 34 E S 20 on SE., S 19 on SW., and S 18 on NW. faces with 3 notches on S. and 5 notches on E. edges. Land, mostly level.