

Subdivisions of T. 3 North, R. 34 East W. M.

| | |
|--------|--|
| Chains | long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face. |
| 39.90 | Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist. Raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S on N. face. |
| 59.85 | Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist. Raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face. |
| 79.80 | Cor. to Secs. 19, 20, 29 and 30. Land, level. Soil, 1st rate. Not cultivated. |
| | West on ran. bet. Secs. 19 and 30. |
| | Va. 20° East. |
| 74.75 | Set temporary cors. at 20, 40 and 60 chains, and at Intersect W. bdy. Township 100 lks. S. of cor. to Secs. 19, 30, 24 and 25. Thence S.89°14' East on true line. |
| | Va. 20 $\frac{1}{2}$ ° East. |
| 14.75 | Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist. Raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face. |
| 34.75 | Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist. Raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S on N. face. |
| 54.75 | Deposited charred stake 12 ins. in the ground for 1/16 |