

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S on N. face.
44.82	Gulch, course S.
59.10	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
79.60	To point of commencement. Land, rolling. Soil, 1st rate. Not cultivated.
<p>East on random through N. $\frac{1}{2}$ of Sec. 36. Va. $20\frac{3}{4}^{\circ}$ East. Commencing at 1/16 sec. cor., 20 chains S. of NW. cor. of Sec. 36 at 20, 40, and 60 chains, and at 79.60 Intersect E. bdy., 60 lks. N. of 1/16 sec. cor. Thence N. $89^{\circ}34'$ West on true line.</p>	
19.90	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
39.80	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit, drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on N. face.
42.00	Enter Indians' field, N. and S.
51.80	Leave same.
59.70	Deposited charred stake 12 ins. in the ground for 1/16

5X