

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
79.40	To point of beginning. Land, gently rolling. Soil, good. Well adapted to cultivation.
East on random through Center of Sec. 24. Va. 21° East.	
79.48	Commencing at $\frac{1}{4}$ sec. cor. bet. Secs. 23 and 24. Set temporary cors. at 20, 40 and 60 chains, and at Intersect E. bdy. 63 lks. N. of $\frac{1}{4}$ sec. cor. Thence N. 89°33' W. on true line.
19.87	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in East pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
29.20	Wagon road, N. and S.
39.74	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S. on N. face.
59.61	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
79.48	To point of beginning. Land, mostly level. Soil, 1st rate.