

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	<p>East on ran. through N <math>\frac{1}{2}</math> of Sec. 24.</p> <p style="text-align: center;">Va. 21° East.</p> <p>Commencing at 1/16 sec. cor., 20 chains N. of <math>\frac{1}{4}</math> sec. cor. bet. Secs. 23 and 24, set temporary cors. at 20, 40 and 60 chains, and at</p> <p>79.52 Intersect E. bdy. 70 lks. N. of 1/16 sec. cor. Thence N.89°30' West on true line.</p> <p>19.88 Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5<math>\frac{1}{2}</math> ft. dist. Raised mound of earth 1<math>\frac{1}{2}</math> ft. high, 3<math>\frac{1}{2}</math> ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p> <p>39.76 Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5<math>\frac{1}{2}</math> ft. dist. Raised mound of earth 1<math>\frac{1}{2}</math> ft. high, 3<math>\frac{1}{2}</math> ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p> <p>59.64 Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5<math>\frac{1}{2}</math> ft. dist. Raised mound of earth 1<math>\frac{1}{2}</math> ft. high, 3<math>\frac{1}{2}</math> ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p> <p>79.52 To point of beginning.</p> <p>Land, level.</p> <p>Soil, 1st rate. Cultivated. Oct. 4, 1887.</p>
	<p>East on random through S <math>\frac{1}{2}</math> Sec. 13.</p> <p style="text-align: center;">Va. 21° East.</p> <p>Commencing at 1/16 sec. cor., 20 chains N. of SW. cor. of Sec. 13. Set temporary cors. at 20, 40 and 60 chains, and at</p> <p>79.44 Intersect E. bdy. 49 lks. N. of 1/16 sec. cor. Thence N.89°39' W. on true line.</p>