

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $1/16$ S W C on N. face.
24.50	Barn and Hay mow 50 ft. wide.
39.77	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{2}$ S on N. face.
59.56	Deposited charred stake 12 ins. in the ground for $1/16$ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $1/16$ S on N. face.
79.42	To point of beginning. Land, mostly level. Soil, good.
East on random through N. $\frac{1}{2}$ of Sec. 13. Va. $20^{\circ}$ East.	
Beginning at $1/16$ sec. cor. 20 chains N. of $\frac{1}{4}$ sec. cor. bet. Secs. 13 and 14, set temporary cors. at 20, 40 and 60 chains, and at	
79.44	Intersect E. bdy. 35 lks. N. of $1/16$ sec. cor. Thence N. $89^{\circ}45'$ West on true line.
19.86	Deposited charred stake 12 ins. in the ground for $1/16$ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit, drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $1/16$ S on N. face.
28.00	Wagon road, N. and S.
32.00	Spring branch, 5 lks. NW course.
39.72	Deposited charred stake 12 ins. in the ground for $1/16$