

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
59.58	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit, drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
79.44	To point of beginning. Land, level. Soil, 1st rate. Cultivated.
East on random through S ½ Sec. 12 Va. 20° East. Beginning at 1/16 sec. cor., 20 chains N. of SW. cor. of Sec. 12, set temporary cors. at 20, 40 and 60 chains, and at	
79.64	Intersect E. bdy. 25 lks. N. of 1/16 sec. cor. Thence N.89°49' W. on true line
19.91	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft., raised mound of earth 1½ ft. high, 3½ base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
39.82	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. East and West of stake, 5½ ft. dist. Raised mound of earth, 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the mound, marked 1/16 S on N. face.
59.73	Set post 3 ft. long, 3 ins. square, 21 ins. in the ground for 1/16 sec. cor., marked 1/16 S on N. face.