

Sub-Subdivisions of T. 3 North, R. 34 East

|   |  |
|---|--|
| Chains  | Beginning at $\frac{1}{4}$ sec. cor., 20 chains N. of $\frac{1}{4}$ sec. cor. bet. Secs. 27 and 27. Set temporary cors. at 20, 40 and 60 chains, and at  |
| 80.30   | Intersect E. bdy. 12 lks. S. of 1/16 sec. cor. Thence S.89°55'W. on true line.   |
| 20.07   | Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist. Raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face. |
| 40.15   | Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist. Raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face. |
| 60.22   | Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist. Raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face. |
| 80.30   | To point of beginning.<br>Land, level.<br>Soil, 1st rate. Cultivated.  |
| East on random through S. $\frac{1}{8}$ of Sec. 23.<br>Va. 20 $\frac{1}{2}$ ° East.   |  |
| Commencing at 1/16 sec. cor., 20 chs. S. of $\frac{1}{4}$ sec. corner, between Secs. 22 and 23, set temporary 1/16 sec. cors. at 20, 40 and 60 chains, and at |  |
| 80.20   | Intersect E. bdy. 10 lks. S. of 1/16 sec. cor. Thence S.89°56' W. on true line.  |
| 20.05   | Deposited charred stake 12 ins. in the ground for 1/16   |