

Sub-Subdivisions of T. 3 North, R.-34 East

Chains	<p>sec. cor. Dug pits 18x18x12 ins. E. and West of stake, 5½ ft. dist. Raised mound of earth, 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
40.10	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
60.15	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth, 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
80.20	<p>To point of beginning. Land, level. Soil, 1st rate.</p>
<p>East on random through S. ½ of Sec. 11 Va. 20° East.</p>	
<p>Beginning at 1/16 sec. cor. 20 chains N. of SW. cor. of Sec. 11, set temporary cors. at 20, 40 and 60 chains, and at.</p>	
80.00	<p>Intersect E. bdy. 14 lks. N. of 1/16 sec. cor. Thence N. 89° 54' W. on true line.</p>
20.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft., 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
38.50	<p>Fence and field, N. and S.</p>
40.00	<p>Deposited charred stake 12 ins. in the ground for 1/16</p>